

V Ý K A Z V Ý M E R

SO 05 – MOKRINY II. – NESPEVNENÁ 4,0/30

šírka = 4,0m, dĺžka = 204,52m

1. Zobratie ornice hr.300mm.....	1 724,00m ²
(viď. tabuľky)	
2. Výkop tr.2- 60%, tr. 3- 40%.....	126,00m ³
(viď. tabuľky)	
3. Násyp.....	237,00m ³
(viď. tabuľky)	
4. Zásyp rigolu.....	81,00m ³
(viď. tabuľky)	
5. Zemná krajnica zo zhutneného nezamŕzavého materiálu.....	26,59m ³
0,13m ² x 204,52m = 26,59m ³	
6. Spevnenie krajnice štrkodrvou, fr. 0 – 22mm, hr. 100mm.....	204,52m ²
(2 x 0,50m) x 204,52m = 204,52m ²	
7. Štrkodrava, fr. 0 – 32mm (cca 100mm).....	61,36m ³
0,30m ² x 204,52m = 61,36m ³	
8. Mechanicky spevnená zemina, (cca 150mm).....	102,26m ³
0,58m ² x 204,52m = 102,26m ³	
9. Zatrávnenie hr.100mm.....celkom.....	1 267,26m ²
9a. Zatrávnenie.....	1 165,00m ²
(viď. tabuľky)	
9b. Zatrávnenie krajnice.....	102,26m ²
(2 x 0,250m) x 204,52m = 102,26m ²	
10. Svahovanie násypu.....	931,00m ²
(viď. tabuľky)	
11. Svahovanie zárezu.....	542,00m ²
(viď. tabuľky)	
12. Úprava pláne.....	1 039,58m ²
5,083m x 204,52m = 1 039,58m ²	

VÝHYBŇA NA CESTE Č. 5 – MOKRINY II. – 1x

- Zobratie ornice, hr. 300mm.....	52,00m ²
- Násyp	13,00m ³
- Spevnenie krajnice štrkodrvou, fr. 0 – 22mm, hr. 100mm.....	16,35m ²
0,50m x 32,70m = 16,35m ²	
- Štrkodrava, fr. 0 – 32mm (cca 100mm).....	5,20m ³
0,10m x 52,00m ² = 5,2m ³	
- Mechanicky spevnená zemina, (cca 150mm).....	7,80m ³
0,15m x 52,00m ² = 7,80m ³	